

TEMPORARY HALF-PIPE RAMP - PRICED BUILD SHEET

Ref TW-HP-001 Rev P01 4 October 2026

NOT A DESIGN - NOT FOR CONSTRUCTION - NOT A PERMIT TO LOAD

Indicative UK supply rates, 4 October 2026, delivered. Excludes overheads, profit, prelims, plant, the design fee, the independent check, the ride inspection regime, and the event insurance.

Description	Qty	Unit	Rate	Amount
A. TIMBER				
Leg 100 x 100 C24 treated, average 1.50 m 2 per cross frame, both sides. Length varies with the transition	36	no	16.50	594.00
Bearer / rail 100 x 75 C24 treated, laid flat 9 runs x 20 m: 3 under the flat, 3 up each transition	180	m	8.20	1,476.00
Cross bearer under the flat, 100 x 75 18 frames x 1.5 m across the flat bottom	27	m	8.20	221.40
B. PLY				
Ply 12 mm exterior, riding surface, two layers 146 m2 surface + 24 m2 deck, doubled = 340 m2, plus cutting waste	115	sheet	38.00	4,370.00
Ply 18 mm exterior, side and end closing About 76 m2 closing so nobody can get inside the structure	26	sheet	46.00	1,196.00
Ply 18 mm, curved ribs, 300 mm deep 36 ribs in two segments each, nested 4 segments per sheet	20	sheet	46.00	920.00
Ply 18 mm spreader pads 450 x 450 under every leg 36 pads, cut from 7 sheets	7	sheet	46.00	322.00
C. STEEL				
Coping tube 60 mm dia, both top edges 2 x 20 m, with end caps and fixings to the deck	40	m	18.00	720.00
Screw and bolt fixings, coping, ribs to rails, ply to ribs Allowance: about 4,000 screws at 150 c/c plus M10 bolts	1	item	620.00	620.00
D. BALLAST				
Ballast to hold the ramp down, see the calc sheet 5 t in the middle of the 3.0-6.8 t range. Concrete blocks or water ballast	5	t	130.00	650.00
Ground anchors, alternative to ballast if the tarmac may be broken Priced as nil. Cheaper if the ground allows - CHECK before ordering ballast	0	no	0.00	0.00
E. LABOUR				
Carpenter 2 carpenters x 5 days: cut ribs, frame, deck, surface, closing	10	day	245.00	2,450.00
General labourer Assisting, handling sheets, ballast	4	day	185.00	740.00
Materials, steel and ballast				11,089.40
Labour				3,190.00
TOTAL - excludes overheads, profit and prelims				14,279.40
Rate per metre of ramp (20 m long)				713.97

WHAT THE PRICE DOES NOT INCLUDE

- Overheads, profit and prelims. Plant and transport of a 20 m structure.
- The temporary works design and its independent check - that is the designer's fee.
- The ride inspection regime and the load test required before it opens to the public.
- Event insurance, supervision, marshalling, or the site's own traffic management.
- Ground anchors: priced at nil, because if the ground allows them they replace the ballast.
- Any change if the site comes back inland, or the shape factor lands higher than assumed.

Rates are indicative. Replace them with the rate book before this is used commercially.